

CHAPTER 7(Damp Proof Course)

Sl.No	Description Of Work	Unit	Rate			
			Full item Rate			Labour Rate
			Jalaun	Jhansi	Lalitpur	
1	2	3	4	5	6	7
360	2 cm (3/4") thick damp proof coarse with cement and approved coarse sand 1:2 with and including water proofing material as ordered by the Engineer-in-charge in the proportion as specified by the manufacturers. including supply of all materials, labour and T&P etc. required for proper completion of the work and including proper curing and shuttering as necessary	sqm	184.00	179.10	188.90	29.70
361	As in item (360) above but 2.5 cm. (1") thick and of cement concrete consisting of one part cement 1.5 parts approved coarse sand and 3 parts approved 13 mm. (1/2") graded stone grit and including waterproofing materials as ordered by the Engineer-in-charge in the proportion as specified by the manufacturers.	sqm	276.20	260.50	274.60	110.40
New Item						
1	Providing and laying damp proof course 2.5 cm thick with cement concrete 1:2:4 (1 cement:2 coarse sand:4 graded stone aggregate 10 mm nominal size) and curing complete	sqm	317.20	297.70	315.20	110.40
2	Painting on D.P.C. with two coats of air blown bitumen 85/50 or 85/25 @ 1.7 Kg/Sqm approx including cost of fuel if any.	sqm	90.00	90.00	90.00	5.00

(Er. Shripal Singh)

Superintending Engineer
Jhansi Circle, P.W.D., Jhansi

22.07.2014
S.E. CD