

CHAPTER-15
PAINTING AND DISTEMPERING

Sl. No.	DESCRIPTION OF ITEMS	UNIT	Jalaun	Jhansi	Lalitpur	Labour Rate
1	2	3	4	5	6	7
641	Painting or Varnishing on iron works in small areas or new wood work with one coat of ready mixed priming paint & one coat of approved superior quality ready mixed paint of clear synthetic varnish including supply of all materials, labour and T&P etc. required for proper completion of the work. Paint to be used should confirm to the I.S.I.No. 103 1950	Sqm.	63.80	63.80	63.80	19.10
642	Same as in Item 641 above but for every coat after 1 st Coat. Details of cost for 650 sft. Area.	Sqm.	29.40	29.40	29.40	8.80
643	As in Item 642 above but for every coat on previously painted old wood or steel work.	Sqm.	40.00	40.00	40.00	12.00
644	Painting roofs or other iron work in large area with one coat of ready mixed paint priming one coat of approved paint (British ANTISOL) including supply of all materials, labour & T&P etc. required for proper completion of the work. Paint to be used should confirm I.S.I.No. 103-1950. Cost for area of 650 Sft. Priming Coat.	Sqm.	50.00	50.00	50.00	15.00
645	As in Item No. 644 above but every coat after the first coat.	Sqm.	23.10	23.10	23.10	6.90
646	As in Item No. 645 above but every coat on previously painted old surface.	Sqm.	32.50	32.50	32.50	9.80
649	One priming coat & one coat oil distemper on new work including supply of all materials, labour and T&P etc. required for proper completion of the work.	Sqm.	45.00	45.00	45.00	13.50
650	As in item No.649 above but for every coat after the first coat.	Sqm.	23.10	23.10	23.10	6.90
651	As in item No.650 above but for every coat on previously old distempered surface.	Sqm.	26.90	26.90	26.90	8.10
652	One coat hot coaltar on new surface including supply of all materials, labour and T&P etc. required for proper completion of the work.	Sqm.	18.10	18.10	18.10	5.40
653	One coat hot coaltar but every coat after 1st coat previously painted surface including supply of all materials, labour and T&P etc. required for proper completion of the work.	Sqm.	12.50	12.50	12.50	3.80
654	One coat solignum or other approved preservative on new wood. Including supply of all material, labour and T&P etc. required for proper completion of the work.	Sqm.	35.00	35.00	35.00	10.50
655	As in item No.654 above but for every coat after first coat or on previously treated surface.	Sqm.	26.30	26.30	26.30	7.90
656	Oiling wood work with double boiled linseed oil including supply of all materials, labour and T&P etc. required for proper completion of the work. Details for an area of 700 sqft.	Sqm.	11.90	11.90	11.90	3.60

S.E (D)

(AS)

[Signature]

