

CHAPTER 11

MISCELLANEOUS ITEMS

Schedule Item No.	Description of Item	Unit	Complete Rate	Labour Rate
1101	Supply and fixing of call bell of approved make on polished MDFEG / Teak ply board including making connections etc. complete in all respect.	each	125.00	30.00
1102	Supply and fixing of door chime on polished MDFEG / Teak ply board including making connections etc. complete in all respect.	each	160.00	30.00
1103	Supply and fixing of buzzer on polished MDFEG / Teak ply board including making connections etc. complete in all respect.	each	110.00	30.00
1104	Supply and fixing of 2 ways bell indicator on polished MDFEG / Teak ply board including making connections etc. complete in all respect.	each	360.00	60.00
1105	Supply and fixing of 3 ways bell indicator on polished MDFEG / Teak ply board including making connections etc. complete in all respect.	each	390.00	60.00
1106	Supply and fixing of 4 ways bell indicator on polished MDFEG / Teak ply board including making connections etc. complete in all respect.	each	475.00	75.00
1107	Supply and fixing of 5 ways bell indicator on polished MDFEG / Teak ply board including making connections etc. complete in all respect.	each	535.00	75.00
1108	Supply and fixing of 6 ways bell indicator on polished MDFEG / Teak ply board including making connections etc. complete in all respect.	each	595.00	75.00
1109	Supply and fixing of danger board fabricated from 10 gauge M.S. Sheet as per I.E. Rules.	each	70.00	30.00
1111	Supply and fixing of 15A 240 Volts I.C. cut out of approved make on the Metre board or polished MDFEG / Teak ply board. complete in all respect.	each	62.00	20.00
1112	Supply and fixing of 32A 240 volts I.C. cut out of approved make on the Metre board or polished MDFEG / Teak ply board. complete in all respect.	each	110.00	20.00
1112(A)	Supply and fixing of 63A 240 volts I.C. cut out of approved make on the Metre board or polished MDFEG / Teak ply board. complete in all respect.	each	160.00	24.00
1113	Supply and fixing of square G.I. earth connecting strip complete with holes for earth leads and clamping screws as directed complete in all respects :			
	(a) Suitable for 2 nos. earth leads	each	23.00	17.00
	(b) Suitable for 3 nos. earth leads	each	30.00	17.00

Schedule Item No.	Description of Item	Unit	Complete Rate	Labour Rate
	(c) Suitable for 4 nos. earth leads	each	41.00	17.00
	(d) Suitable for 6 nos. earth leads	each	55.00	20.00
	(e) Suitable for 8 nos. earth leads	each	70.00	20.00
	(f) Suitable for 10 nos. earth leads	each	85.00	24.00
	(g) Suitable for 12 nos. earth leads	each	102.00	24.00
1114 A	Supply and fixing of M.S. box of size 480mm x 480mm x 200mm deep in sunk for housing BDB/TPN fabricated from 16 gauge M.S. Sheet and 13mm x 2.5mm flat iron etc. painted outside with red oxide primer and inside with synthetic enamel paint complete in all respect.	each	930.00	160.00
1114 B	Supply and fixing of M.S. box of size 600mm x 480mm x 200mm deep in sunk for housing BDB/TPN fabricated from 16 gauge M.S. Sheet and 13mm x 2.5mm flat iron etc. painted outside with red oxide primer and inside with synthetic enamel paint complete in all respect.	each	1100.00	160.00
1115	Erection and testing of ceiling fan and regulator etc. excluding supply of down rod, complete in all respect.	each	68.00	50.00
1116	Erection and testing of ceiling fan and regulator for room height up to 3.5 metres including supply of 3mm thick G.I. Pipe 19mm dia. Duly painted, complete in all respect.	each	135.00	60.00
1117	Add extra to item (1116) for 15cm or part thereof for room height from 3.5 to 5.00 metres.	each	25.00	--
1118	Add extra to item (1116) for 15cm or part thereof for room height from more than 5.00 metres.	each	35.00	--
1119	Add extra to item (1116) to (1118) for flushing of regulators.	each	30.00	--
1120	Erection and testing of exhaust fan on the existing hole with suitable size of rag bolts, nuts and washers etc., complete in all respect.	each	130.00	99.00
1121	Making hole in the wall for exhaust fan and finishing properly complete in all respect.	each	325.00	290.00
1122	Supply and fixing of 16 gauge M.S. drum duly painted including making hole in the wall for exhaust fan and finishing properly complete in all respect.	each	680.00	180.00
1122 (A)	Supply and fixing of 16 SWG M.S. drum with luvors duly painted including making hole in the wall for exhaust fan and finishing properly complete in all respect.	Each	950.00	180.00
1123	Supply and fixing of fan hook fabricated from M.S. rod for ceiling fan each.	each	105.00	180.00
1124	Supply and fixing of cross clamp of required size fabricated from 50mm x 12mm M.S. flat complete with fan hook including painting etc. complete in all respect.	each	240.00	55.00
1125	Supply and fixing of polished MDFEG / Teak ply cover for surface type I.C. switch complete with 50mm hinges, aluminium kunda, chhapka and handle etc. complete in all respect.	each	675.00	50.00

Schedule Item No.	Description of Item	Unit	Complete Rate	Labour Rate
1126	Supply and fixing of polished MDF EG / Teak ply cover for surface type B.D.B. 2 ways to 4 ways complete with 50mm hinges aluminium kunda, chhapka and handle etc. complete in all respect.	each	740.00	50.00
1127	Supply and fixing of polished MDF EG / Teak ply cover for surface type B.D.B. above 4 ways complete with 50mm hinges, aluminium kunda, chhapka and handle etc. complete in all respect.	each	800.00	50.00
1128	Supply and fixing of heavy duty cadmium plated copper connector with end plate complete in all respect. (a) Two way connector HKM 100 (b) Three way connector HKM 100 (c) Four way connector HKM 100	each each each	130.00 185.00 237.00	25.00 25.00 25.00
1129	Supply and fixing of crimping, solderless, copper tin electroplated lugs of Dowells/Ismaile make suitable for 1.5 sq.mm to 2.5 sq.mm cables, including tapping with insulating tape, complete in all respect.	each	14.00	6.00
1130	Supply and fixing of crimping, solderless, Dowells/Ismaile make copper tin plated, in line connectors, including tapping with insulating tape, complete in all respect.	Deleted		
1130 A	1.5 to 2.5 sq.mm			
1130 B	4.00 to 6.00 sq.mm			
1130 C	10.00 to 16.00 sq.mm			
1131	Supply and fixing of fire extinguisher ABC Type 4.00 kg. capacity (ISI Marked IS : 15683 & TAC approved) complete with initial charge and wall bracket, along with supply of all materials and labour for proper completion of work.	each	8100.00	30.00
1131 (A)	Supply and fixing of fire extinguisher ABC Type 6.00 kg. capacity (ISI Marked IS : 15683 & TAC approved) complete with initial charge and wall bracket, along with supply of all materials and labour for proper completion of work.	each	9010.00	30.00
1131(B)	Supply and fixing of fire extinguisher ABC Type 9.00 kg. capacity (ISI Marked IS : 15683 & TAC approved) complete with initial charge and wall bracket, along with supply of all materials and labour for proper completion of work.	each	10300.00	30.00
1132	Supply and fixing of CO2 type fire extinguisher 4.5 kg. capacity (ISI Marked IS : 2878 & TAC approved) complete with initial charge and wall bracket, along with supply of all materials and labour for proper completion of work.	each	12300.00	30.00
1132 (A)	Same as in item no. 1132 but of 6.5 kg. capacity	each	18300.00	30.00
1133	Supply and fixing of fire bucket, round bottom made of G.I. sheet 9-11 litres capacity duly painted as per fire brigade design, supported on hanging bracket chained and locked, initially filled with fine river sand, water as per directions of Engineer-in-Charge.	each	350.00	94.00

Schedule Item No.	Description of Item	Unit	Complete Rate	Labour Rate
1134	Supply and fixing of shock treatment chart (prescribed under I.E. rules) duly framed with glass and supported from back with hard board or soft board with supply of all material labour T&P for proper completion of work.	each	235.00	20.00
1135	Supply and fixing of 600mm x 600mm size polished MDFEG / Teak ply cover fabricated from 19mm thick block board with one phase polished, fixed with 75mm hinges on to 65mm x 20mm size PMDFEG / Teak wood chowkhat including aluminium anodized handle of suitable size kunda, chhapka, etc. with all material labour T&P etc. required for proper completion of work.	each	860.00	90.00
1136	Supply and laying of 1800mm x 900mm x 12mm thick chequered rubber matting of tested quality.	each	2525.00	17.00
1137	Supply and fixing of power plug with 15A/250V tumbler switch with porcelain base and 3 pin 15A/250V socket with porcelain base on PMDFEG / Teak ply double board.	Deleted		
1138	Supply and fixing of power plug with 16A/240V ICDP switch (B-category) and 3 pin 15A/250V socket with porcelain base on well seasoned PMDFEG / Teak ply double board.	Deleted		
1139	Supply and fixing of power plug with 15A/250 volt flush type switch and 5 pin 15A/250V flush type universal socket in suitable M.S. box of 175mm x 100mm x 50mm size with phenolic laminated bakelite sheet cover 3mm thick fixed with brass machine screw and cup washer.	each	270.00	75.00
1139 (A)	Supply and fixing of power plug with 20 Amp./250 volt flush type modular switch and 5 pin 20 A/250 volt flush type universal modular socket switch on concealed M.S box including supply of all material, labour T&P etc. required for proper completion of work.	each	595.00	75.00
1140	Supply and fixing of interlock metal-clad switch socket and plug combined unit. Fixed on wall with rag bolts and nuts including supply of all material, labour T&P etc. required for proper completion of work.	Deleted		
1141(A)	Construction of recess of 480mm x 480mm x 200mm size for fixing of main boards, distribution boards of all sizes including cutting of brick work, providing lintel of suitable size and thickness, plastering etc. with supply of all materials labour T&P for proper completion of work.	each	375.00	230.00
1141(B)	Construction of recess of 600mm x 480mm x 200mm size of main boards, distribution boards of all sizes including cutting of brick work, providing lintel of suitable size and thickness, plastering etc. with supply of all materials labour T&P required for proper completion of work.	each	480.00	271.00

Schedule Item No.	Description of Item	Unit	Complete Rate	Labour Rate
1142	Supply and fixing of 2 metres high cage fabricated with 3mm thick expanded metal fixed on 50mm x 50mm x 6mm angle iron frame having vertical members spaced at 1 to 1.25 mts and horizontal members spaced at 1 mt. The vertical members shall be grouted in floor and horizontal members in the wall to a depth of 300mm with ends forked. The cage shall have 2000mm x 1000mm size one leaf door with locking device having door frame fabricated with 35mm x 35mm x 6mm angle iron and 3mm expanded metal duly fixed with the cage member with hinges etc. The cage shall be painted with red oxide primer and synthetic enamel paint. The job includes all materials labour, T&P etc. for proper completion of work.	Per Sq. mts.	1020.00	135.00
1143	Add for fixing of tube fittings as pendent with two number 19mm dia. 16 gauge rigid steel conduit double check nuts : spring loaded flanges or M.S. hook fabricated from 25mm x 3mm flat iron duly grouted in the ceiling upto 3.5 height of ceiling, including painting with synthetic enamel paint. Along with supply of all materials labour, T&P etc. required for proper completion of work.	each	235.00	76.00
1144	Add extra to item No. 1143 for 15cm or part thereof for room height above 3.5m.	each	45.00	27.00
1145	Supply and fixing of single leaf factory fabricated M.S. cover with mounting frame for 480mm x 480mm x 200mm size sunk fabricated from 18 SWG M.S. sheet duly painted with red oxide primer followed by two coats of synthetic enamel spray paint complete with steel almirah type handle and locking arrangements and fixed with hold fasts etc. including supply of all materials, labour and T&P etc. required for proper completion of work.	each	1120.00	168.00
1146	Supply and fixing of single leaf factory fabricated M.S. cover with mounting frame for 600mm x 480mm x 200mm size sunk fabricated from 18 SWG M.S. sheet duly painted with red oxide primer followed by two coats of synthetic enamel spray paint complete with steel almirah type handle and locking arrangements and fixed with hold fasts etc. including supply of all material labour and T&P etc. required for proper completion of work.	each	1360.00	168.00
1147	Supply and fixing of factory fabricated M.S. box in existing sunk of size 600mm x 480mm x 200mm deep with Godrej type almirah cover with handle etc. fabricated from 18 SWG (1.25mm) M.S. sheet duly painted with red oxide primer followed by two coats of synthetic enamel paint complete with necessary conduit entry and D.P./T.P.N.; fixing arrangements and provision for compartment for loose wires openable housing on the top and hold fast etc. including supply of all material, labour, T&P etc. required for proper completion of the work.	each	1435.00	168.00
1148	Same as in P.S. 1147 but of 480mm x 480mm x 200mm deep size.	each	1305.00	168.00

Schedule Item No.	Description of Item	Unit	Complete Rate	Labour Rate
1149	Supply and fixing hexagonal fan box with hexagonal side of approx 80mm in length fabricated from 16 SWG MS sheet incorporating 10mm dia. M.S. round bar duly bent for supporting fan hanger duly painted with red oxide and screwing arrangement with wiring conduit laid in the R.C.C. roof before concreting along with supply of all material, labour, T&P etc. required for proper completion of the work.	each	135.00	30.00
1150	Painting of conduit pipe assorted size two coat, laid for telephone (Green) of fire lighting (red) etc. by synthetic enamel paint including all material, labour, T&P etc. required for proper completion of the work.	each	10.00	4.00
1151	Deleted			
1152	Deleted			
"NCT" Flo-coat Electrical Tubings, Fittings and Accessories (conforming to I.S.S.)				
N.B. : These shall be used in Govt. Electrical Works for open spaces, underground. Damp place and chemically effected places only.				
1153	Supply and fixing of 20mm dia conduit on surface on wall with necessary bends. Tees, elbows, Couplers, cap and spacers including all the required materials, T&P labour etc. for proper completion of work.		Deleted	
1154	As above in P.S. No. 1153 but 25mm dia		Deleted	
1155	As above in P.S. No. 1153 but 32mm dia		Deleted	
1156	Supply and fixing of galvanised round junction boxes of assorted size suitable for above tubing.		Deleted	
1157	Deduct in P.S. No. 148 to 152 for laying of conduit pipe in the ground 900mm below including the cost of digging the trench and refilling the excavated earth making joints water tight with zinc-white or red lead.		Deleted	