

Chapter 6							
BRICK WORK							
(For Building Work Only)							
S.No.	Sch. PWD	Item No. NBO	Description of item	P.W.D. Spec. No.	Unit	Labour Rate	Over All Rate
1	303		M-150 brick work in 1:6 cement and sand of 1.25 fineness modulus mortar in foundation and plinth including supply of all material, labour and tools and plants. ect. required for proper completion of work.	6.1.1	Cum	510.00	4393.00
2	304		As in item 303 above but in 1:5 cement and coarse sand of 1.25 fineness modulus mortar	6.1.2	Cum	510.00	4450.00
3	305		As in item 303 above but in 1:4 cement and fine sand of 1.25 fineness modulus mortar	6.1.3	Cum	510.00	4800.00
	305 (B)		As in item 305 above but for Coarse sand in 1:4	6.1.3	Cum	510.00	5070.00
4	306		As in item 303 above but in 1:3 cement and sand of 1.25 fineness modulus mortar	6.1.4	Cum	510.00	4925.00
5	307		As in item 303 above but in 1:3 cement and coarse sand mortar.	6.1.5	Cum	510.00	5200.00
6	309		As in item 302 to 307 above but in super structure including necessary cutting and moulding of bricks required and also including honey comb brick work, thickness of walls more than one brick and for extra lab our to above items.	6.1.6 6.2.2 6.3.2 6.2.4	Cum	210.00	
7	310		Same as item No. (309) above but for one brick wall add for extra lab our.		Cum	210.00	
	a		As in item 309 above but walls of half brick 11.5 mm (4-1/2") thick add for extra lab our over item no. 310.	6.1.7 6.2.3	Cum	95.00	
	b		As in item 309 above but walls of half brick 75 mm (3") thick add for extra lab our over item No. 310(a)	6.1.7 6.2.7	Cum	125.00	
8	319		11.5 cm. (4-1/2") thick string or drip coarse with 6 cm (2-1/4") thick projection of M-150 brick work in 1:6 cement and sand of 1.25 F.M. including 12mm thick plaster in 1:6 cement and sand of 1.25 F.M. with simple moulding and cutting drip notch as required including and supply of all materials, labour T&P etc. required for proper completion of work.	6.7.2	R.M.	65.00	70.00
9	321		As in item 319 above but for 9" cornice in three courses with 6 cm projection in each course in 1:6 cement and sand (of 1.25 fineness modulus) mortar.	6.4	R.M.	75.00	115.00
10	322		Extra cutting of brick for moduling as required for cornice etc. including rubbed finish not exceeding 11.5cm (4-1/2") width (lab our only)	6.7.4	R.M.	45.00	46.00

11	323		Making opening through walls in lime or cement mortar for door and windows of enlarging existing opening or cutting out brick work for underpinning including necessary supports, staging etc. cleaning site and stacking the dismantled materials at the place as directed by Engineer-in-charge within distance of 60meters (200ft.)	6.8	Cum.	-	830.60
12	327		Add to all items of brick work in super structure extra for B/W in circulars.		Cum.	377.00	1007.00

(Gyan Prakash Pandey)
Superintending Engineer
Azamgarh Circle, P.W.D.,
Azamgarh