

**CHAPTER-4**

**EARTH WORK**

SI No.	SCH P.W.D.	ITEM No.	Description of items of work	P.W.D. Specification	Unit No	Labour Rate
1	2	3	4	5	6	7
1	251		Excavation in foundation in ordinary soil (loamclay or sand) including lift up to 1.5m and lead up to 30m. and including filling watering and ramming of excavated earth into the space between the building and the sides of foundation trenches or into the plinth and removal and disposal of surplus earth as directed by the Engineer in charge up to a distance of 30m. from the foundation trenches including all T&P phowarah and basket etc. complete.	4.1.1	Cum	99.00
4	253		Earth work in cutting or in embankment in ordinary soil excavation to be the form of regular pits not exceeding ½ meter (20") in depth and earth work in embankment to be in 20cm (8") layers, including ramming and dressing the surface to required levels and slopes and also including 1.5m (5") lift and 30m (100') lead. The earth from cutting to be used in making embankment or to be deposited as spoil banks within 30m (100') distance as directed by the E/I.Excluding Cost of Royalty		Cum	80.00

Note : en I 0&1 dh nj i fy; k , oa ukyh fuekzk dh uho [kqkz dsfy; seku; gA

Note : en I 0&2 dh nj xteh.k ekxk ds fuekzk rFk i Vjh fuekzk dsfy; seku; gA

**(Gyan Prakash Pandey)**  
 Superintending Engineer  
 Azamgarh Circle, P.W.D.,  
 Azamgarh