

**Chapter 18****MARBLE WORK IN WALL LINING ETC.**

S.No	Sch. PWD	Item No. NBO	Description of item	P.W.D. Spec. No.	Unit	Labour Rate	Over All Rate
1			Dholpur stone work for wall lining etc. (Veneer work) 40mm thick in cement mortar 1:3(1cement :3coarse sand) including cramping joining in white cement mortar 1:2(1 white cement :2stone dust)with an admixture of pigment matching the stone shade.		Sq.M		959.00
2			Finishing walls with sanctex matt.Coat over a priming coat of water proof cement paint of approved quality such as super"Snowcem" "Durocem" super quality of required shade on undecorated will surface to give an even shade after thoroughly brushing the surface to remove all dirt and remains of loose powered material including curing and cost of all materials labour T & P etc.Complete.		Sq.M		86.50

**(Gyan Prakash Pandey)**  
**Superintending Engineer**  
**Azamgarh Circle, P.W.D.,**  
**Azamgarh**